sted on the notice board in the Executive Engineer's Office in due course. No enquiries garding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be urned.

Abstract of quantities for constructing Sub-Registrar's Office and Bonded Depot at Nelamangala.

No.	Items of work	Per	Quantity	Rate
1	Earthwork excavation	Cyds.	123	
2	Burnt stone jelley in lime mortar concrete ...	C.ft.	672	
3	Burnt stone in clay	,,	2,730	
4	Burnt brick in clay	,,	2,789	
5	Burnt brick in lime mortar	,,	673	
6	Teakwood battened door 1¼" thick shutter including all iron fittings, etc.	S.ft.	137	
7	Teakwood battened door 1¼" thick plank iron fittings with four leaves.	,,	45	
8	Teakwood battened windows 1" thick with ¾" iron bars and all iron fittings.	,,	268	
9	Teakwood glazed ventilators with iron bars, etc., complete.	,,	11	
10	Teakwood work wrought and put up with wood-oiling	C.ft.	78·30	
11	Steel joists including hoisting	Cwt.	35·00	
12	Stone wall plate 4" × 6"	R.ft.	96	
13	Jack arch roofing complete	Sqr.	6·34	
14	Roofing with First Class Mangalore tiles on teak reepers complete.	,,	19·14	
15	Ridge tiles set in mortar	R.ft.	53	
16	Dressed stone pillars for verandah with iron clamps etc.	Each	14	
17	Burnt stone slabs 6" roughly dressed	S.ft.	500	
18	Cornice 9" thick	R.ft.	225	
19	Parapet wall 2' high brick in clay and chunam plastered	,,	118	
20	Flooring with Caddapah slab 1½" thick on 3" concrete bed and cement pointing.	Sqr.	14·76	
21	Teakwood eave board	R.ft.	160	
22	Teakwood finials	Each	2	
23	Teakwood pendents	,,	6	
24	Binding wall over gable	R.ft.	40	
25	Plastering with mortar	Sqr.	67·40	
26	Tarring to wood work	,,	5·00	
27	Chacolate painting	,,	14·60	
28	Cement pointing	,,	2·34	
29	White and colour washing	,,	67·40	
30	Partition between store room and top with iron bars flat iron and angle iron work, complete.	S.ft.	120	

R. W. SCALDWELL,
Executive Engineer.

KOLAR DIVISION.

Dated 17th December 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive gineer, Kolar Division, up to 2 P.M., on 25th January 1928, for restoring Belamaranahalli elinakere Major Tank, R. No. 258 of Kolar Taluk. An approximate estimate of quantities given below. These quantities are not guaranteed. The work should be completed by e end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's fice at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the ecutive Engineer. The tenders should be accompanied by a statement in the form given ow, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 700 in cash or Government Promissory Notes, as earnest money and be superscribed Tender for restoring Belamaranahalli Melinkere Major Tank, Kolar Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore Circle who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be furnished in words as well as in figures.

Items of work	Per	Quantity	Rate	Cost	Total
			Rs.	Rs.	Rs.
Bund R. L. 58·00.					
Earthwork including watering and tamping ...	C.yd.	17,782			
Turfing	S.yd.	6,502			
Removing and resetting old stone revetment ...	C.yd.	598			
New stone revetment	„	1,596			
Grove stones with index stones, cutting figures, painting and fixing.	No.	22			
Inscription stone do do ...	„	1			
B. M. Stones	„	2			
Gauge stone	„	1			
Total ...	..	...	...	...	...
Sluice at R. L. 46·00.					
Earthwork	C.yd.	55			
Surki mortar concrete	C.ft.	105			
Burut brick in surki mortar	„	489			
Plastering with surki mortar	Sqrs.	3·42			
Burnt stone slabs 6" thick	S.ft.	140			
Cutting holes in stone slabs	No.	4			
Providing iron plug rod with locking arrangement complete.	Lump	sum			
Cast iron pipe 5" drain and 9' long	R.ft.	36			
Total ..	..	....	...	...	...
Waste Weir at R. L. 53·00.					
Earthwork	C.yd.	1,028			
Concrete in surki mortar	C.ft.	1,006			
Burnt brick in surki mortar	„	3,622			
Plastering with surki mortar	Sqrs.	23·40			
Burnt stone slabs 6"	S.ft.	432			
New rough stone revetment for apron ...	C.yd.	563			
Total ..	..	..	..	...	...
Grand Total ...	...	..	..	...	...

N. G. KRISHNA IYENGAR,
Executive Engineer.

6 B